BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK_INDENT34389/CALL-2

Maintenance of cremortorium Burial ground and office maintenance in Ward No.11 Kuvempunagara

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. D V Kumar	
				In figures	In words
1	952.50	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications.	Cum	200.00	Rupees Two Hundred Only
2	635.00	KSRRB M300- Construction of Embankment with Material Gravel / Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel / Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller)	Cum	400.00	Rupees Four Hundred Only
3	15.00	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification	Sqm	3200.00	Rupees Three Thousand Two Hundred Only
4	2.59	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.	Cum	500.00	Rupees Five Hundred Only
5	0.65	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6000.00	Rupees Six Thousand Only
6	12.00	Supply and erection of 14 Feet Height Street Light Pole on suitable cement concrete foundation with 2.5 Feet height cast iron decorative round pedestal as per design weighing not less than 37Kgs, the pedestal shall be fitted with Class 'C' G.I.Pipe 7 Feet height 75mm outer dia and 4 feet height top piece outer dia of 65mm fixed by measure of threading/ welding / coupling complete. (excluding foundation).	Each	22000.00	Rupees Twenty Two Thousand Only

D.V.K

Contractor

Executive Engineer 25/7/19
Project Division
Yelahanka Zone

	tity	Item Name	Unit	Rates quoted by Sri. D V Kumar	
				In figures	In words
	4.32	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6000.00	Rupees Six Thousand Only
8	12.00	Supplying and fixing of solar lux level street light control switch three phase including suitable capacity contactor	Each	21370.25	Rupees Twenty One Thousand Three Hundred Seventy And Paise Twenty Five Only
9	12.00	Extra for Fabrication supply and fixing of Stand fabricated using slotted angle/L angle of size 6mm x 50mm for mounting out door/indoor A.C. unit./ Batteries.	Each	2800.00	Rupees Two Thousand Eight Hundred Only
10	12.00	Supplying surface mounted type mirror optic luminaries for single/Twin 28watts fluorescent lamps cross rising of stove enameled deep coloured M.S.low profile housing complete with all accessories and high purity anodized aluminum reflector assembling along with cross louvers including necessary fluorescent tubes with Energy Saving Electronic Ballast.	Each	4028.00	Rupees Four Thousand Twenty Eight Only
11	12.00	Fixing charges of post top/ Gate/ Garden fitting /LED on the existing CI / GI or any other pipe using required size of reducer, wiring using suitable wires	Each	145.00	Rupees One Hundred Forty Five Only
12	72.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A.	Mtr.	63.80	Rupees Sixty Three And Paise Eighty Only
13	150.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.	Mtr	78.00	Rupees Seventy Eight Only
14	150.00	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV.	Mtr	204.00	Rupees Two Hundred Four Only
15	150.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.	Mtr	140.00	Rupees One Hundred Forty Only
16	2.00	Supplying and fixing Microprocessor based Electronic timer (without contactor, Din Mounting using necessary bolts, nuts and washers etc.,.) 3-120sec	Each	2186.00	Rupees Two Thousand One Hundred Eighty Six Only
17		GST @ 12% (For SR 2018-19 Items Only)			

Executive Engineer
Project Division
Yelahanka Zone
25/7/19

D V J K R
Contractor